

CITY OF CLEVELAND

Mayor Frank G. Jackson

Anthony Brancatelli , Council Member, Ward 12 Brian J. Cummins, Council Member, Ward 14

Matthew Spronz, P.E., Director Mayor's Office of Capital Projects

Richard J. Switalski, P.E., Administration Bureau Manager Division of Engineering and Construction

PUBLIC INFORMATION MEETING

for the

Denison Avenue Utility Upgrade and Repaving Project

held on Thursday, January 9, 2014 @ 6:30 PM At Saxon's Hall, 7001 Denison Avenue

AGENDA

- Introductions and Opening Remarks (Councilpersons/CDC)
- Project Funding and Schedule (C. O.C. Capital Projects)
- Project Description (Middough and C.O.C. Engineering)
- <u>Construction Phasing and Maintenance of Traffic</u> (C.O.C. Engineering and Perk)
- Question and Answers
- Closing Remarks
- Plan Viewing

Agencies represented:

- City of Cleveland Division of Engineering & Construction
- Cleveland Public Power
- · Cuyahoga County Engineers
- Middough, Inc. Design Consultant
- Detroit Shoreway Community Development Office

Project Contacts:

(246) 657-0997 David McAllen (Project Inspector): (216) 905-1515 Frank Keehl, P.E., (Project Manager): (216) 664-2256

Khalil Ewais, P.E. (Chief Construction Engineer): (216) 664-7422

Denison Project Limits:

- Denison Avenue from Ridge Road to State Route 176 (Jennings Freeway)
- West 62nd Street from Barberton Road to Denison Avenue

Purpose of the Meeting:

The purpose of the meeting is to inform the public about the Denison Avenue Utility Upgrade and Repaving Project construction project and to answer questions that the public may have regarding the impacts of the project work on their properties.

Project Construction Costs and Funding Sources: \$9,100,000

• Cleveland Public Power \$7,000,000

• City of Cleveland \$1,250,000

• Cuyahoga County \$850,000

Project Work Scope:

- A new CPP duct bank is to be installed underground along Denison Avenue from W62nd to SR176, Jennings Freeway and along West 62nd Street from the railroad property south of Barberton Avenue to Denison Avenue.
- · Associated utility facility relocations.
- · Pavement base repairs.
- Pavement resurfacing.
- Repair of curb, sidewalk and driveways, where necessary.
- Replacement of existing catch basins, where necessary.
- Installation of ADA compliant ramps at all intersections.
- Placement of pavement markings, including bike lanes/sharrows.

Anticipated Project Schedule and Maintenance of Traffic:

- Phase 1A· West 62nd to Fulton
 Phase 1B· Ridge to West 62nd
 Phase 2· Fulton to Pearl
 Phase 3· Pearl to S.R. 176
 January to August, 2014
 August, 2014 to April, 2015
 April to December, 2015
- Vehicular and pedestrian traffic will be maintained during construction.
- One way traffic will be maintained at all times along Denison.
- Traffic will be maintained to all businesses and residences.
- Signed detour routes along Clark will be provided for traffic travelling in the direction of the closed lanes.

Denison Avenue Underground Ductbank and Resurfacing: Ridge Road to Denison Bridge over State Route 176

